# GTSWCA AGM April 21<sup>st</sup> 2017

Anthony Parente Director, WW




#### 2<sup>nd</sup> Largest Municipality in Ontario

- 1,244 km<sup>2</sup> area
- Population:
  - 800,000 (1991)
  - 1,300,000 (2011)
  - 2,300,000 (Projected 2031)

#### Peel Wastewater Infrastructure:

- 2 Major WWTPs
- 36 Sewage pumping facilities,
- 2 Storm pumping facilities
- 2 Communal treatment plants
- Servicing to York
  - Approx. 53 ML/d
- Servicing to Toronto
  - Approx. 50 ML/d
- 3541km of san. Sewers
- -52,000 + MH's
- 307,000+ customeraccounts

# Region of Peel





# Region of Peel Wastewater Org Structure

#### **Capital Works – Linear**

- Responsible for all linear works in collection system
- Includes State of Good Repair (SOGR)
- Includes large TrunkSewers

Simon Hopton



#### **Capital Works – Treatment**

- Responsible for Treatment Capital
- Includes major maintenance and replacement projects
- Includes a lot of pipe!

John Glass



## New 2400 Dia. Inlet Sewer



# Upcoming Work – 2017

Project Description	Project Manager	Project Status	Estimated Construction Cost	RFT Anticipated Date	Anticipated Construction Start Date
Sanitary sewer replacements: Ponytrail and Rathburn	Derek Gorzynski	Design	\$15,000,000	May-17	July, 2017
900mm sanitary sewer on Dixie Road and crossing QEW	Jimmy Chong	Design	\$10,000,000	May-17	July, 2017
Sanitary Sewer Spot Repairs on various streets within the Region, sanitary sewer main and laterals sealing and spot repairs	Joanna Pietkiewicz	Design	\$3,000,000	May-17	July, 2017
Rehabilitation of sanitary sewer and manholes along the Lornewood Creek from Streambank Dr. to Queen St.	Grace Krasowski	Design	\$3,500,000	Jun-17	Aug-17
Relining of various sanitary sewers	Derek Gorzynski	Design	\$2,000,000	Aug-17	Oct-17
Sanitary sewermain and lateral connection replacements on various streets; joint with w/m contract	Joanna Pietkiewicz	Design	\$1,500,000	Sep-17	Nov-17
Diversion of Cooksville Creek sewer to CPR Interceptor - part of Burnhamthorpe water and sewer tender packages	Grace Krasowski	Design	\$3,500,000	Oct-17	2018/2019
New Sanitary trunk sewer - part of Burnhamthorpe water and sewer tender packages	Grace Krasowski	Design	\$23,000,000	Oct-17	2018
Rehabilitation of sanitary manholes across Peel	Lesley Radman	RFP/ RFQ/ Procurement	\$5,000,000	Dec-17	Mar-18
			\$66,500,000		

Region of Peel
Working for you

# Design Work – 2017/18

Project	Value	Anticipated Construction Year
SOGR Replacement/ Relining Program	\$20-\$25M / year	Yearly, 10 year program +
East to West Collector	\$180M +	2019/2020
Cawthra Diversion	\$42M	2019/2020
Lakeshore West	\$40M	2020?
Pump Station Replacement (Various)	\$40M	2018

# Coming Soon...

Project	Value	Anticipated Construction Year
Manhole Rehabilitation Program	\$5M/ year?	Yearly, 10 year program +
I/I Rehabilitation Program	\$5M/ year?	Yearly, 10 year program +
Trunk Sewer Rehabilitation Program	\$??M/ year	TBD

# WASTEWATER DESIGN/ CONSTRUCTION STANDARDS




Institut de prévention des sinistres catastrophiques Bâtir des communautés résilientes

#### Best practices guide:

Management of inflow and infiltration in new urban developments

By Ted Kesik February 2015





In many ways, inflow and infiltration in new sanitary sewer systems are a barometer of the quality, care and stewardship underlying the municipality, its system of governance, the community's planning vision and its infrastructure engineering excellence.

What can be said about a 21st century civilization that cannot properly design, construct and sustain its vital infrastructure?

Hopefully, it is a question that should not have to be answered by future generations of Canadians.







#### WHY.. Infiltration













### 1200mm - NEW - Beechwood





5 Joints in 171m long Section of pipe failed

## WHY.. Climate Change



- Significant overland flow and surcharging event
- Significant basement flooding in Mississauga and some parts of Brampton
- Plant washouts and bypassing

**Normal** 

This is Mississauga
July 2013

#### WHY.. Intensification



- Increasing demand on existing infrastructure to accommodate increased population density.
- · Inability to convey flows overland
- Increased reliance on sanitary flows parking garages, common areas which cannot be conveyed to storm sewers


#### STANDARDS SUMMARY

- NEW SMALL DIA.
   CONSTRUCTION
  - Standard Gravity < 24"</li>
  - More robust requirements
- NEW LARGE DIA.
   CONSTRUCTION
  - Pressure Design
  - Low pressure testing to 50 psi
- DETAILS
- REHABILITATION


#### **Drawing Count**

- 13 Deleted
  - 3 Updated
  - 3 Pending
  - **63 NEW**





### New Construction – Non-pressure



STRAIGHT THROUGH 825mm FOR RIGHT ANGLE (STD. DWG, 2-5-21)


#### **Key Improvements**

- Less dramatic amendments
- Frame and cover
  - Modified design
  - **Exterior** sealing
  - Sealed covers in vulnerable areas
- Exterior joint sealing
- Pipe to manhole modifications
- Sealed vent stacks
- Flood-safe devices

#### **APPLICATION**

Services up to 600mm Diameter


#### New Standards – Details



# New Construction – *Pressure*Tements Design


#### **Key Improvements**

- Pressure design below tapers
- 24" (600mm) and above only (PROPOSED)
- Proposed pressure 50 psi at Pipe CL
- Working on setting pressure requirements
- AWWA C301/C302 design basis – will permit both
- MH Tee permitted
- Will incorporate pressure testing requirements
- May require closure pieces – same as water
- Balance of gravity design applications



#### Rehabilitation


DIAMETER VARIES



IF BASE SECTION JOINT EXPO REHABILITATION OF BENCHIN OR CRACKS WITH INJECTED H

#### **Key Improvements**

- Multiple level standard
  - 1. ROW
  - 2. Easement/Floodplain installation
  - 3. Excavation/ NO Excavation (ie. Internal or External MH repairs)
- Selected by Designer
- Standard design permitted
- Recognize that significant portion of problem lies in frame/cover and adjustment units
- Secondary issue of significance is Pipe to MH connection




#### Web Site

lumber	Title	PDF :
	Printing Instructions	
info	Printing notes	
2-0	Overall General Notes	
2-0-1	Overall General Notes	399 KI
2-1	Maintemance Holes	
2-1-1	Precast Maintenance Hole 1200mm diameter (DELETED)	180 KI
2-1-2	Precast Maintenance Hole 1500mm and 1800mm diameter (DELETED)	177 K
2-1-3	Precast Maintenance Hole Tees (DELETED)	123 K
2-1-4	Maintenance Hole Benching Details (DELETED)	112 KE
2-1-5	Maintenance Hole Drop Structure - External Assembly (DELETED)	144 K
2-1-6	Maintenance Hole Drop Structure - Internal Assembly (DELETED)	102 K
2-1-7	Maintenance Hole Venting Details (DELETED)	85 KE
2-2	Maintenance Hole Fittings	
2-2-1	Safety Platform for 1200mm dia. Precast Maintenance Hole (DELETED)	144 K
2-2-2	Standard Heavy Duty Frame and Cover (DELETED)	82 KE
2-2-3	Water Tight Maintenance Hole Frame and Cover (DELETED)	90 KE
	Detail of Anchoring Method for Water Tight Maintenance Hole - Steel or Aluminum Strap	
2-2-3A	(DELETED)	71KB
2-2-3B	Detail of Anchoring Method for Water Tight Maintenance Hole - Threaded Rod (DELETED)	68 KE
2-2-4	intenance Hole Steps - Aluminum (DELETED)	100 K
2-3	Bedding and Backfill	
2-3-1	Bedo. Qetails for Sanitary Sewer (NEW)	316 K
2-4	Service Connections	
2-4-1	Service Connaions For Rigid Pipe	152 K
2-4-1	Service Connects For Rigid Pipe Low to Medium Density (UPDATED) PENDING APPROV	/A 217 K
2-4-2	Service Connection or Flexible Pipe	148 K
2-4-2	Service Connections Pexible Pipe Low to Medium Density (UPDATED) PENDING APPR	<b>O√</b> 228 K
	Service Connections For Sele or Rigid Pipe Industrial, Commercial or Institutional	
2-4-3	(NEW) PENDING APPRO	282 K
2-4-4	Service Connection Extensions ( Development) (UPDATED)	
2-4-5	Grinder Pump to Low Pressure (UPA ED)	
2-4-6	Grinder Pump to Low Pressure - The Rolllowance (UPDATED)	
- 4 -	ED)	193 K
	(NEW)	
	A STATE OF THE STA	510 K
_		

WATER TIGHT MAINTENANCE HOLE

- Currently on-line
- Previous versions of drawings will still be accessible but clearly direct a path to new version
- Main page will clearly identify changes



199 KB 178 KB

# Next Steps - Standards

#### Feedback/ Concerns

- THANK YOU for your feedback to date
- Please email concerns (red penned PDF of drawing) direct to Chris Smith, Project Manager – <u>chris.smith@peelregion.ca</u>
- Continuous improvement goal
- Revisions will be issued and revision index maintained
- Revision frequency and Web page update cycle (TBD)

# THANK YOU